


0301 CABLE TIE



Material Specification:

Natural Nylon:

KSS standard cable ties made from U.L. approved nylon 6/6.

Normal service temperature range: -40°C to 85°C. Flammability rating: UL 94V-2.

Black Nylon:

(Material and temperature as above) Except in black color.

For your order please add "B" to standard item no. i.e.CV-075B.

Weather Resistant Nylon(ULTRA VIOLET):

Carbonate "A" was added for greater resistance to ultra violet light in outdoor application.



For your order, please add "W" to standard item no. i.e. CV-075W

Heat Stabilized Nylon:



Service temp. 135°C




Specification:


Made to comply with mil-spec drawing no. MS-3367 tensile strength meet or exceed MIL-S-23190E standard.

Unit:mm	Item No.				L		W	Max. Bundle Dia.	Min. Tensile Strength	
	Natural		Black		m.m.	inch	m.m.	m.m.	lbs(kgs)	
	100 pcs	1000 pcs	100 pcs	1000 pcs						
	<input type="checkbox"/> CV-060	<input type="checkbox"/> CV-060K	<input type="checkbox"/> CV-060B	<input type="checkbox"/> CV-060KB	63.7	2 1/2"	2.4	12	18 (8)	MINIATURE
	<input type="checkbox"/> CV-075	<input type="checkbox"/> CV-075K	<input type="checkbox"/> CV-075B	<input type="checkbox"/> CV-075KB	75	3"	2.4	18	18 (8)	MINIATURE
	<input type="checkbox"/> CV-080	<input type="checkbox"/> CV-080K	<input type="checkbox"/> CV-080B	<input type="checkbox"/> CV-080KB	80	3 1/8"	2.4	19	18 (8)	MINIATURE
	<input type="checkbox"/> CV-094	<input type="checkbox"/> CV-094K	<input type="checkbox"/> CV-094B	<input type="checkbox"/> CV-094KB	96	3 3/4"	2.5	23	18 (8)	MINIATURE
	<input type="checkbox"/> CV-100	<input type="checkbox"/> CV-100K	<input type="checkbox"/> CV-100B	<input type="checkbox"/> CV-100KB	100	4"	2.5	25	18 (8)	MINIATURE
	<input type="checkbox"/> CV-120S	<input type="checkbox"/> CV-120SK	<input type="checkbox"/> CV-120SB	<input type="checkbox"/> CV-120SKB	120	4 3/4"	2.5	30	18 (8)	MINIATURE

	<input type="checkbox"/> CV-140S	<input type="checkbox"/> CV-140SK	<input type="checkbox"/> CV-140SB	<input type="checkbox"/> CV-140SKB	142	5 1/2"	2.5	35	18 (8)	MINIATURE
NEW	<input type="checkbox"/> CV-150S	<input type="checkbox"/> CV-150SK	<input type="checkbox"/> CV-150SB	<input type="checkbox"/> CV-150SKB	155	6 1/8"	2.5	39	18 (8)	MINIATURE
	<input type="checkbox"/> CV-165	<input type="checkbox"/> CV-165K	<input type="checkbox"/> CV-165B	<input type="checkbox"/> CV-165KB	165	6 1/2"	2.5	44	18 (8)	MINIATURE
	<input type="checkbox"/> CV-200M	<input type="checkbox"/> CV-200MK	<input type="checkbox"/> CV-200MB	<input type="checkbox"/> CV-200MKB	203	8"	2.5	55	18 (8)	MINIATURE
NEW	<input type="checkbox"/> CV-400S		<input type="checkbox"/> CV-400SB		400	15 3/4"	2.5	117	18 (8)	MINIATURE
	<input type="checkbox"/> CV-120	<input type="checkbox"/> CV-120K	<input type="checkbox"/> CV-120B	<input type="checkbox"/> CV-120KB	120	4 3/4"	3.2	30	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-140	<input type="checkbox"/> CV-140K	<input type="checkbox"/> CV-140B	<input type="checkbox"/> CV-140KB	142	5 1/2"	3.2	35	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-150	<input type="checkbox"/> CV-150K	<input type="checkbox"/> CV-150B	<input type="checkbox"/> CV-150KB	150	6"	3.6	39	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-180	<input type="checkbox"/> CV-180K	<input type="checkbox"/> CV-180B	<input type="checkbox"/> CV-180KB	180	7"	3.6	49	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-200S	<input type="checkbox"/> CV-200SK	<input type="checkbox"/> CV-200SB	<input type="checkbox"/> CV-200SKB	203	8"	3.2	55	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-200A	<input type="checkbox"/> CV-200AK	<input type="checkbox"/> CV-200AB	<input type="checkbox"/> CV-200AKB	203	8"	3.6	55	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-250M	<input type="checkbox"/> CV-250MK	<input type="checkbox"/> CV-250MB	<input type="checkbox"/> CV-250MKB	250	10"	3.6	74	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-265	<input type="checkbox"/> CV-265K	<input type="checkbox"/> CV-265B	<input type="checkbox"/> CV-265KB	265	10 1/2"	3.6	78	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-292	<input type="checkbox"/> CV-292K	<input type="checkbox"/> CV-292B	<input type="checkbox"/> CV-292KB	292	11 1/2"	3.6	85	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-330		<input type="checkbox"/> CV-330B		330	13"	3.6	96	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-368S		<input type="checkbox"/> CV-368SB		368	14 1/2"	3.6	102	40 (18)	INTERMEDIATE
	<input type="checkbox"/> CV-120L	<input type="checkbox"/> CV-120LK	<input type="checkbox"/> CV-120LB	<input type="checkbox"/> CV-120LKB	120	4 3/4"	4.8	30	50 (22)	STANDARD

	<input type="checkbox"/> CV-160L	<input type="checkbox"/> CV-160LK	<input type="checkbox"/> CV-160LB	<input type="checkbox"/> CV-160LKB	160	6 1/4"	4.8	42	50 (22)	STANDARD
	<input type="checkbox"/> CV-190	<input type="checkbox"/> CV-190K	<input type="checkbox"/> CV-190B	<input type="checkbox"/> CV-190KB	190	7 1/2"	4.8	52	50 (22)	STANDARD
	<input type="checkbox"/> CV-200	<input type="checkbox"/> CV-200K	<input type="checkbox"/> CV-200B	<input type="checkbox"/> CV-200KB	203	8"	4.6	55	50 (22)	STANDARD
	<input type="checkbox"/> CV-250	<input type="checkbox"/> CV-250K	<input type="checkbox"/> CV-250B	<input type="checkbox"/> CV-250KB	250	10"	4.8	74	50 (22)	STANDARD
	<input type="checkbox"/> CV-280	<input type="checkbox"/> CV-280K	<input type="checkbox"/> CV-280B	<input type="checkbox"/> CV-280KB	280	11"	4.8	81	50 (22)	STANDARD
	<input type="checkbox"/> CV-300S		<input type="checkbox"/> CV-300SB		300	11 5/8"	4.8	85	50 (22)	STANDARD
	<input type="checkbox"/> CV-310		<input type="checkbox"/> CV-310B		310	12"	4.8	89	50 (22)	STANDARD
	<input type="checkbox"/> CV-368		<input type="checkbox"/> CV-368B		368	14 1/2"	4.8	102	50 (22)	STANDARD
	<input type="checkbox"/> CV-385		<input type="checkbox"/> CV-385B		385	15 3/16"	4.8	116	50 (22)	STANDARD
	<input type="checkbox"/> CV-432		<input type="checkbox"/> CV-432B		432	17"	4.8	125	50 (22)	STANDARD
	<input type="checkbox"/> CV-450M		<input type="checkbox"/> CV-450MB		450	17 3/4"	4.8	130	50 (22)	STANDARD
	<input type="checkbox"/> CV-500		<input type="checkbox"/> CV-500B		500	19 11/16"	4.8	150	50 (22)	STANDARD
	<input type="checkbox"/> CV-550S		<input type="checkbox"/> CV-550SB		550	21 11/16"	4.8	166	50 (22)	STANDARD
	<input type="checkbox"/> CV-914S		<input type="checkbox"/> CV-914SB		914	36"	4.8	270	50 (22)	STANDARD
	<input type="checkbox"/> CV-120LL	<input type="checkbox"/> CV-120LLK	<input type="checkbox"/> CV-120LLB	<input type="checkbox"/> CV-120LLKB	120	4 3/4"	7.6	30	120 (55)	HEAVY DUTY
	<input type="checkbox"/> CV-150L	<input type="checkbox"/> CV-150LK	<input type="checkbox"/> CV-150LB	<input type="checkbox"/> CV-150LKB	150	6"	7.6	39	120 (55)	HEAVY DUTY
	<input type="checkbox"/> CV-200L	<input type="checkbox"/> CV-200LK	<input type="checkbox"/> CV-200LB	<input type="checkbox"/> CV-200LKB	203	8"	7.6	55	120 (55)	HEAVY DUTY
	<input type="checkbox"/> CV-240L	<input type="checkbox"/> CV-240LK	<input type="checkbox"/> CV-240LB	<input type="checkbox"/> CV-240LKB	240	9 7/16"	7.6	66	120 (55)	HEAVY DUTY

	<input type="checkbox"/> CV-280L	<input type="checkbox"/> CV-280LK	<input type="checkbox"/> CV-280LB	<input type="checkbox"/> CV-280LKB	280	11"	7.6	78	120 (55)	HEAVY DUTY
	<input type="checkbox"/> CV-300		<input type="checkbox"/> CV-300B		300	11 7/8"	7.6	88	120 (55)	HEAVY DUTY
	<input type="checkbox"/> CV-340		<input type="checkbox"/> CV-340B		340	13 1/2"	7.6	99	120 (55)	HEAVY DUTY
	<input type="checkbox"/> CV-380				380	15"	7.6	110	120 (55)	HEAVY DUTY
	<input type="checkbox"/> CV-380S		<input type="checkbox"/> CV-380SB		380	15"	6.4	110	45 (20)	HEAVY DUTY
		<input type="checkbox"/> CV-380B		380	15"	7.6	110	120 (55)	HEAVY DUTY	
	<input type="checkbox"/> CV-450		<input type="checkbox"/> CV-450B		450	17 3/4"	8.0	133	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV-500L		<input type="checkbox"/> CV-500LB		500	19 11/16"	8.0	150	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV-550		<input type="checkbox"/> CV-550B		550	21 11/16"	8.0	166	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV-610		<input type="checkbox"/> CV-610B		605	24"	9.0	185	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV-685		<input type="checkbox"/> CV-685B		680	27"	9.0	210	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV-710		<input type="checkbox"/> CV-710B		705	28"	9.0	220	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV-762		<input type="checkbox"/> CV-762B		762	30"	9.0	236	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV-812		<input type="checkbox"/> CV-812B		812	32"	9.0	246	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV-914		<input type="checkbox"/> CV-914B		914	36"	9.0	270	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV-		<input type="checkbox"/> CV-		950	37"	9.0	285	175 (80)	HEAVY DUTY

	940		940B							
	<input type="checkbox"/> CV- 1168		<input type="checkbox"/> CV- 1168B		1168	46"	9.0	360	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV- 1219		<input type="checkbox"/> CV- 1219B		1219	48"	9.0	380	175 (80)	HEAVY DUTY
	<input type="checkbox"/> CV- 1500		<input type="checkbox"/> CV- 1500B		1500	59"	9.0	464	175 (80)	HEAVY DUTY
